

NOTE:

MOULDED TEES ARE REQUIRED FOR ALL LATERALS ON NEW SEWER LINES. ALL LATERALS SHALL BE SCHEDULE 40 PIPE AND JOINTS SHALL BE GLUED WITH AN APPROVED ADHESIVE.

